


Status of the Cosmic Ray Test Stand at UF

Holger Stöck
University of Florida




Chamber Setup


2 chambers
and
3 rows of
scintillators

Scintillator

ME 2/1
20 degrees

ME 234/1
10 degrees





Scintillator Trigger Setup

Top scintillator


- two panels
- both read out


Middle/bottom scintillator

- one panel
- two PMTs
- one PMT read out

Trigger for L1Accept

- any three of four PMTs
- includes always one top panel
- L1A rate ~ 4 Hz





Peripheral Crate Setup


TMB/DMB for
ME 2/1 with 9m
blue cables


DDU

MPC

CCB with
TTCrm

TMB/DMB for
ME 234/1 with
11m black cables






TrackFinder Crate Setup


TTCvx/TTCvi

MPC for
in-Crate tests

CCB with
TTCrq

SectorProcessor





DAQ Setup


DAQ PC

- 1 GB RAM (512 MB BigPhys)
- 80 GB HD for CSC data
- Connects to PC via Dynatem and to TFC via SBS VME controllers
- Control programs
 - PC: cfeb_control
 - TFC: TFGUI and console programs
- Needs tuning

Three Terminal PCs


- For access to DAQ PC






Test Stand Status

- **Approx. 75% of L1A in coincidence with LCT from ME 234/1 - Rate is improving with time (Gas flushing)**
- **ME 2/1 less efficient than ME 234/1
Efficiency is improving with time (Gas flushing)**
- **Data transfer between DDU and DAQ PC working**
- **Data transfer between MPC/PC and SP/TFC working**
- **Setup for data transfer between SP and DAQ PC in progress**
- **LCT-L1A delay timing done**
- **PHOS4 timing in progress**



Changes to Testbeam Setup

- **ME 2/1**
 - **cfeb_control ALCT code changed to account for chamber type #3**
 - **New ALCT threshold and delay setting files**
- **New timing values for both chambers**
- **L1A trigger rate by a factor of 100 lower**
- **Lower L1A trigger rate will make it difficult to test system saturation (DAQ PC, software)**



To Do

- **Finish timing-in of chambers**
- **Fine tuning of chamber setup (Scintillator/HV)**
- **Finish setup of data transfer between SP and DAQ PC**
- **Verify data quality**
- **Setup software for Slice Test working group**
- **...**